

Renovation of 3' x 6' Powder Room



Scope of Work

Demolition – removal of existing toilet, vanity, countertop, sink, faucet, glass mirror, tile floor, wallpaper and lighting.
Renovation – new flooring (ceramic floor tile, bullnose tile floor trim, marble threshold, grout and caulk), new paint (paint prep and priming, wall patching, and ceiling, wall, trim and door painting), plumbing (new toilet, flange and wax gasket, relocated water lines for sink, new water shut-off valves for sink and toilet), electrical (new pendant drop light, light switch, electrical outlet and face plates), and installation (vanity, sink, faucets, towel bars and rings).